

140688
ADDENDUM NO.2

DATE: May 17, 2018

FROM: Baxter & Woodman, Inc. Consulting Engineers

TO: Plan holders of record for the Work titled

VILLAGE OF RANTOUL - WILLOW POND ROAD

The Bidding Documents are amended as follows:

1) CONTRACT PROPOSAL – SCHEDULE OF PRICES

Delete the Schedule of Prices in its entirety and replace with the attached Schedule of Prices.

DELETED the following pay items to the Schedule of Prices:

- 20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER) UNIT 45
- 20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER) UNIT 75
- 20101200 TREE ROOT PRUNING EACH 10
- 20101100 TREE TRUNK PROTECTION EACH 10

REVISED the following pay items to the Schedule of Prices:

- 550A0050 STORM SEWERS, CLASS A, TYPE 1 12" FOOT from quantity **50 to 202**
- 60218400 MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID EACH from **3 to 1**
- 25200200 SUPPLEMENTAL WATERING UNIT from **115 to 10**

(Quantities for Tree Removal and Tree Pruning and Tree Trunk Protection are nominal quantities and not required).

This revision adds acknowledgement of the Addendum.

2) PLANS

Delete Summary of Quantities Sheets No. 4-6 in its entirety from the plans and replace with attached Revised (dated 5/17/18) :

DELETED the following pay items to the Schedule of Prices:

- 20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER) UNIT 45
- 20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER) UNIT 75
- 20101200 TREE ROOT PRUNING EACH 10
- 20101100 TREE TRUNK PROTECTION EACH 10

REVISED the following pay items to the Schedule of Prices:

- 550A0050 STORM SEWERS, CLASS A, TYPE 1 12" FOOT from quantity **50 to 202**
- 60218400 MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID EACH from **3 to 1**
- 25200200 SUPPLEMENTAL WATERING UNIT from **115 to 10**
- Fixed 2nd table on Sheet No. 6 to show the correct columns. Total quantities not affected.

This revision adds acknowledgement of the Addendum.

Nothing in this Addendum shall be construed as changing other requirements of the Bidding Documents. Each Bidder shall acknowledge receipt of this Addendum where indicated in the Bid Form.

Bidder acknowledges receipt of ADDENDUM No. 2: _____

END OF ADDENDUM NO.2

ADDENDUM NO.2
140688



SCHEDULE OF PRICES

County Champaign
 Local Public Agency Village of Rantoul
 Section N/A
 Route Willow Pond Road

Schedule for Multiple Bids

Combination Letter	Sections Included in Combinations	Total

Schedule for Single Bid

(For complete information covering these items, see plans and specifications)

Bidder's Proposal for making Entire Improvements

Item No.	Items	Unit	Quantity	Unit Price	Total
20200100	EARTH EXCAVATION	CU YD	1085		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1175		
20800150	TRENCH BACKFILL	CU YD	40		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1065		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2533		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	51		
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	51		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	51		
25100630	EROSION CONTROL BLANKET	SQ YD	2533		
25200200	SUPPLEMENTAL WATERING	UNIT	9		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	56		
28000510	INLET FILTERS	EACH	8		
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	750		
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	312		

RETURN WITH BID

Bidder's Proposal for making Entire Improvements

Item No.	Items	Unit	Quantity	Unit Price	Total
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	4259		
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	9583		
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	7439		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13		
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5, N50	TON	358		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	178		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	737		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1219		
42001300	PROTECTIVE COAT	SQ YD	878		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2686		
42400800	DETECTABLE WARNINGS	SQ FT	240		
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	8321		
44000100	PAVEMENT REMOVAL	SQ YD	5041		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	5007		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1315		
44000600	SIDEWALK REMOVAL	SQ FT	2833		
44201690	CLASS D PATCHES, TYPE I, 4 INCH	SQ YD	5		
44201692	CLASS D PATCHES, TYPE II, 4 INCH	SQ YD	96		
44201694	CLASS D PATCHES, TYPE III, 4 INCH	SQ YD	161		
44201696	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	310		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	167		

RETURN WITH BID

Bidder's Proposal for making Entire Improvements

Item No.	Items	Unit	Quantity	Unit Price	Total
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	202		
55100300	STORM SEWER REMOVAL 8"	FOOT	21		
55100500	STORM SEWER REMOVAL 12"	FOOT	52		
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1		
60255700	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2		
60255900	MANHOLES TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	3		
60266600	VALVE BOXES TO BE ADJUSTED	EACH	3		
60500040	REMOVING MANHOLES	EACH	4		
60500060	REMOVING INLETS	EACH	1		
60600605	CONCRETE CURB, TYPE B	FOOT	25		
60602800	CONCRETE GUTTER, TYPE B	FOOT	637		
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1619		
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	105		
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1		
66900530	SOIL DISPOSAL ANALYSIS	EACH	3		
67100100	MOBILIZATION	L SUM	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5906		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2752		

RETURN WITH BID

Bidder's Proposal for making Entire Improvements

Item No.	Items	Unit	Quantity	Unit Price	Total
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		
72000100	SIGN PANEL - TYPE 1	SQ FT	248		
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	31		
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	2		
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	54		
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	310		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	87		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4224		
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1133		
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	408		
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	141		
A2000114	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	2		
A2003114	TREE, CELTIS OCCIDENTALIS WINDY CITY (WINDY CITY HACKBERRY), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	2		
A2008518	TREE, ULMUS MORTON GLOSSY (TRIUMPH ELM), 2" CALIPER, BALLED AND BURLAPPED	EACH	2		
C2000548	SHRUB, ARONIA MELANOCARPA (BLACK CHOKE BERRY), 4' HEIGHT, BALLED AND BURLAPPED	EACH	8		
C2005812	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), 2' HEIGHT, BALLED AND BURLAPPED	EACH	8		
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	40		
X2500920	SEEDING, CLASS 1A (SPECIAL)	ACRE	1		

RETURN WITH BID

Bidder's Proposal for making Entire Improvements

Item No.	Items	Unit	Quantity	Unit Price	Total
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	19		
X4023000	TEMPORARY ACCESS (ROAD)	EACH	13		
X4400196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	119		
X4400220	CURB REMOVAL AND REPLACEMENT	FOOT	152		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	3312		
X6026056	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	9		
X6026630	VALVE BOXES TO BE MOVED	EACH	1		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	390		

COPYRIGHT © 2014 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. - 184-00121 - EXPIRES 4/30/2015
 488ccc 5/17/2018 4:35:58 PM
 ...\\pictdr\pdf-fw_Default.plt
 ...\\CADD\Plots\140688_PEN.tbl
 i:\Mokem\RANTL\140688-Will Pond Rd Recon\CADD\Drawings\DNS\140688_S001.shx

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0004 - ROADWAY	
				RESURFACE	RECONSTRUCT
20200100	EARTH EXCAVATION	CU YD	1085		1085
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1175		1175
20800150	TRENCH BACKFILL	CU YD	40		40
21001000	GEO TECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1065		1065
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2533	1013	1520
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	51	22	29
* 25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	51	22	29
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	51	22	29
* 25100630	EROSION CONTROL BLANKET	SQ YD	2533	1013	1520
* 25200200	SUPPLEMENTAL WATERING	UNIT	9	4	5
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	56	24	32
* 28000510	INLET FILTERS	EACH	8	4	4
SP 30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	750		750
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	312	279	33
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	4259		4259

* DENOTES SPECIALITY ITEM
 SP DENOTES ITEMS COVERED BY SPECIAL PROVISIONS

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0004 - ROADWAY	
				RESURFACE	RECONSTRUCT
SP 40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	9582.8		9582.8
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	7438.6	5617.0	1821.6
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13	13	
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5, N50	TON	358	358	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	178	178	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	737		737
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1219	822	397
42001300	PROTECTIVE COAT	SQ YD	878	599	279
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2686	2414	272
42400800	DETECTABLE WARNINGS	SQ FT	240	240	
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	8321	8321	
44000100	PAVEMENT REMOVAL	SQ YD	5041		5041
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	5007	5007	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1315	856	459
44000600	SIDEWALK REMOVAL	SQ FT	2833	2434	399

* DENOTES SPECIALITY ITEM
 SP DENOTES ITEMS COVERED BY SPECIAL PROVISIONS



DESIGNED - JDW	REVISED - ADDENDUM NO. 2 REV 5-17-2018
DRAWN - BCD	REVISED -
CHECKED - CAC	REVISED -
DATE - 05-04-18	FILE - 140688_S001.shx

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ STA. _____ TO STA. _____

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHAMPAIGN	53	4
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

COPYRIGHT © 2014 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. - 184-00121 - EXPIRES 4/30/2015
 488ccc 5/17/2018 4:37:22 PM
 i:\Mokema\RA\NTL\140688-Will Pond Rd Recon\CADD\Drawings\DNS\140688_S002.sht

	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0004 - ROADWAY	
					RESURFACE	RECONSTRUCT
SP	44201690	CLASS D PATCHES, TYPE I, 4 INCH	SQ YD	5	5	
SP	44201692	CLASS D PATCHES, TYPE II, 4 INCH	SQ YD	96	96	
SP	44201694	CLASS D PATCHES, TYPE III, 4 INCH	SQ YD	161	161	
SP	44201696	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	310	310	
	48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	167	167	
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	202		202
	55100300	STORM SEWER REMOVAL 8"	FOOT	21		21
	55100500	STORM SEWER REMOVAL 12"	FOOT	52		52
	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2		2
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1
	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1		1
	60255700	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2		2
	60255900	MANHOLES TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	3	3	
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	3	2	1
	60500040	REMOVING MANHOLES	EACH	4	3	1

* DENOTES SPECIALITY ITEM
 SP DENOTES ITEMS COVERED BY SPECIAL PROVISIONS

	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0004 - ROADWAY	
					RESURFACE	RECONSTRUCT
	60500060	REMOVING INLETS	EACH	1		1
	60600605	CONCRETE CURB, TYPE B	FOOT	25		25
	60602800	CONCRETE GUTTER, TYPE B	FOOT	637	311	326
	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1619	1005	614
	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	105		105
	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1		1
	66900530	SOIL DISPOSAL ANALYSIS	EACH	3		3
	67100100	MOBILIZATION	L SUM	1		1
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	5906	3486	2420
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2752	1740	1012
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1
	72000100	SIGN PANEL - TYPE 1	SQ FT	248	209	39
	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	31	22	9
	72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	2	

* DENOTES SPECIALITY ITEM
 SP DENOTES ITEMS COVERED BY SPECIAL PROVISIONS



DESIGNED - JDW	REVISED - ADDENDUM NO. 2 REV 5-17-2018
DRAWN - BCD	REVISED -
CHECKED - CAC	REVISED -
DATE - 05-04-18	FILE - 140688_S002.sht

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ STA. _____ TO STA. _____

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHAMPAIGN	53	5
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

COPYRIGHT © 2014 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. - 184-00121 - EXPIRES 4/30/2015
 488ccc 5/17/2018 4:37:48 PM
 ...\\cadd\plots\40688_PEN.tbl
 ...\\cadd\plots\40688_PEN.tbl
 \\corp.boxwood.com\projects\Mokena\NANTL\40688-WilliPond Rd Recon\CADD\Drawings\DGNS\40688_S003.shx

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0004 - ROADWAY	
				RESURFACE	RECONSTRUCT
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	54	54	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	310	220	90
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	87	82	5
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4224	2092	2132
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1133	1093	40
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	408	188	220
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	141	113	28
* A2000114	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	2		2
* A2003114	TREE, CELTIS OCCIDENTALIS WNDY CITY (WNDY CITY HACKBERRY), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	2		2
* A2008518	TREE, ULMUS MORTON GLOSSY (TRIUMPH ELM), 2" CALIPER, BALLED AND BURLAPPED	EACH	2		2
* C2000548	SHRUB, ARONIA MELANOCARPA (BLACK CHOKE BERRY), 4' HEIGHT, BALLED AND BURLAPPED	EACH	8		8
* C2005812	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), 2' HEIGHT, BALLED AND BURLAPPED	EACH	8		8
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	40		40
SP * X2500920	SEEDING, CLASS 1A (SPECIAL)	ACRE	1.0	0.6	0.4
SP X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	19	13	6

* DENOTES SPECIALITY ITEM
 SP DENOTES ITEMS COVERED BY SPECIAL PROVISIONS

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0004 - ROADWAY	
				RESURFACE	RECONSTRUCT
SP X4023000	TEMPORARY ACCESS (ROAD)	EACH	13	12	1
SP X4400196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	119	119	
SP X4400220	CURB REMOVAL AND REPLACEMENT	FOOT	152	61	91
SP X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	3312	3312	
SP X6026056	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	9	6	3
SP X6026630	VALVE BOXES TO BE MOVED	EACH	1		1
SP Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1
SP Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	390	312	78

* DENOTES SPECIALITY ITEM
 SP DENOTES ITEMS COVERED BY SPECIAL PROVISIONS



DESIGNED - JDW	REVISED - ADDENDUM NO. 2 REV 5-17-2018
DRAWN - BCD	REVISED -
CHECKED - CAC	REVISED -
DATE - 05-04-18	FILE - 140688_S003.shx

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ STA. _____ TO STA. _____

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHAMPAIGN	53	6
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO.	